



SOLICITATION TO BID

PROJECT: ENGINEERING AND INSTALLATION OF UPSTREAM DEBRIS BOOM

Indianford Dam
Lake Koshkonong, Wisconsin

Bid Submission

Bids must be postmarked by May 13, 2024 at 5:00 p.m. CST
Rock Koshkonong Lake District
PO Box 63
Edgerton, WI 53534
ATTN: Mark Meyer, Treasurer

Pre-Bid Tour

April 22, 2024 at 10:00 a.m., CST
Indianford Dam Powerhouse
3893 West County Rd M, Edgerton, WI 53534

PROJECT: ENGINEERING AND INSTALLATION OF UPSTREAM DEBRIS BOOM

INDIANFORD DAM

LAKE KOSHKONONG, WISCONSIN

BID SUBMISSION: Bids must be postmarked by May 13, 2024, at 5:00 p.m. CST and mailed to the following address:

**Rock Koshkonong Lake District
PO Box 63
Edgerton, WI 53534
ATTN: Mark Meyer, Treasurer**

OWNER: Rock Koshkonong Lake District (hereinafter RKLD)

All potential bidders and employees of bidders must be trained and/or certified as defined and required by the Occupational Health and Safety Administration (hereinafter OSHA). All bids from contractors who fail to follow this requirement will be rejected.

The project is let using the design-build process. Base bids will be received as a single lump sum. Any bids that fail to list a lump sum will not be accepted. RKLD will identify and select the lower, qualified, responsible bidder.

Sealed bids will be accepted as follows, before the time indicated above: The bidder is responsible for delivering the sealed bid to the location described above, or by email by the deadline for bid submission. Bidder has the sole responsibility for delivering the bids by the deadline

Once the lowest bid has been identified and selected, the RKLD will award the project to said lowest bidder on May 16, 2024. Successful Contractor shall provide applicable license and proof of insurance upon notification of award.

Generally, the work will consist of the following: The contractor will design and install a debris boom using the existing anchor points. The debris boom will be constructed using materials supplied by RKLD. The project will require relocation of the power house and connection closer to the spillway and surveying of the anchor points to design a system that will tension the boom consistently as it moves vertically. Contractor will provide the anchors and/or the first link to the debris boom and will add floats as needed. The contractor will also be responsible for obtaining the approval of the Wisconsin Department of Natural Resources (hereinafter DNR). All work shall be compliant with state, local, and environmental regulations.

The following specifications must be followed: First, connections to the existing anchors must allow for the debris boom to move a minimum of six (6) feet vertically to allow for changes in the water level. The installation must be reasonable based on estimated water levels of 776-782 as prescribed by the National Geodetic Vertical Datum of 1929 (hereinafter NGVD29). The design will be 150% of the debris boom hardware load rating. The following deadlines will apply after the award has been made: design specifications are due by June 24, 2024. Installation must begin by July 24, 2024, and shall be completed by August 24, 2024.

Bidding documents will be handed out at the pre-bid tour and all documents will be posted at www.rkld.org as they become available.

Pre-Bid Tour: A pre-bid tour will be held on April 22, 2024, at 10:00 a.m. CST. at the Indianford Dam located at 3893 West County Rd M, Edgerton, WI 53534. Material lists and conceptual drawings will be distributed and discussed at this meeting.

Interested bidders, please call or email RKLD Board of Commissioner Treasurer Mark for additional information, (608) 728-1838, markmeyer3966@gmail.com.